# SECTION V - MITIGATION STRATEGY

### LOCAL HAZARD MITIGATION GOALS

Requirement §201.6(c)(3)(i):	The hazard mitigation strategy shall include a] description of mitigation goals to reduce
	or avoid long-term vulnerabilities to the identified hazards.

The following pages contain goals and strategic mitigation actions for each of the hazards identified earlier in this plan, followed by a town-by-town summary of prioritized projects. Within the municipalities, their priorities are based on local knowledge of their risks/vulnerabilities and available budget and potential funding to address them. If a town wishes to apply for grant funding, officials understand that they will need to use FEMA's Benefit/Cost Analysis (BCA) process and the County will support their efforts by providing information and/or guidance.

The goals for the 2017 Plan remain the same. Because Maine is a home rule State and counties can only promote and educate to specific activities, some objectives have been deleted.

The following presents a list of the mitigation goals and actions planned to reduce or avoid long-term vulnerability in the County thereby reducing the impact of natural disasters on people, property, a infrastructure, and the environment.

Goal #1: Reduce damage, injury and loss of life resulting from flooding in Cumberland County.

Hazard: Flooding			
Actions	Time Frame	Status	Responsible Party
1.1 Provide information to the public concerning the dangers of flooding through brochures (such as those from the National Weather Service) posted on the county website and social media, (measured through "hits" and "engagements" on these sites) and distributed at public events (See Appendix for samples of brochures)	Annually and As Needed	New	ССЕМА
1.2 Review Emergency Action Plans for High and Significant Hazard dams on an annual basis and update contact information	Annually	Completed As Planned and Ongoing	CCEMA/LEMD
1.3 Provide Flood insurance Program updates to local EMA directors and town officials through local director meetings and monthly newsletter	An needed	New	ССЕМА
1.4 Promote community participation in NFIP's Community Rating System through local director meetings monthly newsletter and community outreach	Annually	Completed As Planned and Ongoing	ССЕМА
1.5 Provide information to local directors and town officials about green infrastructure solutions to urban runoff/flooding through local director meetings and monthly newsletter	Annually	New	ССЕМА
1.6 Promote river/stream corridor and wetland protection through education of local EMA directors and municipal officials, and monthly newsletter.	Annually	Completed As Planned and Ongoing	ССЕМА

Goal #2: Reduce damage, injury and loss of life resulting from severe summer and winter storms in Cumberland County.

Hazard: Severe Summer and Winter Storms						
Action	Timeframe	Status	Responsible Party			
2.1 Provide information to the public concerning the dangers of severe summer and winter storms through hazard-specific brochures (such as those from the National Weather Service) posted on the county website and social media, (measured through "hits" and "engagements" on these sites) and distributed at public events (See Appendix)	Annually and As Needed	New	ССЕМА			
2.2 Support towns and eligible non-profits in applying for generator grants to protect their critical functions	Annually	New	CCEMA/LEMD			
2.3 Use social media and Vulnerable Population Communication Network to inform public of impending storms/hazardous conditions (See Appendix)	As needed	New	CCEMA			
2.4 Track mitigation projects through surveys with local EMA directors/Public Works directors	Annually	New	CCEMA/LEMD			
2.5 Support municipalities in development/maintenance of warming/cooling center plans	Annually	New	ССЕМА			

## Goal #3: Reduce damage, injury and loss of life resulting from wildfires in Cumberland County

Hazard: Wildfires					
Action	Timeframe	Status	Responsible Party		
3.1 Promote participation in wildfire prevention programs such as FireWise through local director meetings, monthly newsletter and community outreach	Annually	New	CCEMA/LEMD/TO		
3.2 Promote participation in Maine Forest Service workshops and consultations through education of local directors and municipal officials through local director meetings and monthly newsletter.	Annually and As Needed	New	CCEMA/LEMD		
3.3 Provide information to the public concerning the dangers of wildfires through brochures (such as those from the National Weather Service and the Maine Forest Service) posted on the county website and social media, (measured through "hits" and "engagements" on these sites) and distributed at public events	Annually and As Needed	New	CCEMA		

Goal #4 Reduce damage, injury and loss of life resulting from coastal erosion in Cumberland County.

Hazard: Coastal Erosion			
Action	Timeframe	Status	Responsible Party
4.1 Update local emergency managers concerning storm surge mapping and relevant evacuation zones	Annually and As Needed	New	CCEMA
4.2 Inform local emergency management directors of grant availability for mitigation of vulnerable infrastructure	When Available	New	CCEMA

### CUMBERLAND COUNTY HAZARD MITIGATION PLAN

4.3Work with local emergency managers and town officials to develop a tracking methodology for coastal erosion separately from other storm damages	Annually and As Needed	New	CCEMA/LEMD/TO
--	---------------------------	-----	---------------

#### **IDENTIFICATION AND ANALYSIS OF MITIGATION ACTIONS**

Requirement §201.6(c)(3)(ii):	The mitigation strategy shall include a] section that identifies and analyzes a comprehensive range of specific mitigation actions and projects being considered to reduce the effects of each hazard, with particular emphasis on new and existing buildings and infrastructure.
Requirement §201.6(c)(3)(ii):	[The mitigation strategy] must also address the jurisdiction's participation in the National Flood Insurance Program (NFIP), and continued compliance with NFIP requirements, as appropriate.
Requirement §201.6(c)(3)(iii):	[The mitigation strategy shall include] an action plan describing how the actions identified in section (c)(3)(ii) will be prioritized, implemented, and administered by the local jurisdictions. Prioritization shall include a special emphasis on the extent to which benefits are maximized according to a cost benefit review of the proposed projects and their associated costs.
Requirement §201.6(c)(3)(iv):	For multi-jurisdictional plans, there must be identifiable action items specific to the jurisdiction requesting FEMA approval or credit of the plan.

Currently, all 28 communities within Cumberland County participate in the National Flood Insurance Program (NFIP). Their continued compliance with the program is encouraged at all levels of the County's mitigation strategy. Two communities participate in the Community Rating System at Level Eight (Portland and Cape Elizabeth. Each community will continue to enforce its existing floodplain ordinance

The list of local projects contained in the following table was developed and prioritized separately by each municipality. Projects were chosen based on local knowledge of the frequency and extent of local damages, local knowledge of which projects were of the highest priority (based on frequency and severity of damages), local knowledge of weather, the geography and topography of the community, and the technical and financial abilities of their respective communities to address hazards and mitigate the impacts of hazards. Municipal capabilities could expand if other funding were to become available.

Many of the municipalities in Cumberland County are small towns that do not have the resources, staff or funding to prepare cost benefit analyses for their proposed projects. However, in virtually all cases involving expenditure of local funds for implementation, there will be a very rigorous, line-by-line analysis of cost effectiveness during the budget review process and subsequent public discussion through regular and special meetings. This review is at least equal to a formal benefit-cost calculation because each expenditure item will be scrutinized rather than simply plugged into a formula. Furthermore, MEMA and CCEMA have made it clear to local officials that a formal cost-benefit analysis must be prepared when they apply for mitigation funding.

The list of projects contained in the table below is largely the result of Cumberland County EMA's collaboration with town officials, local EMA, and Public Works officials to first review and update their hazard mitigation project lists, and secondly, to continue their ongoing efforts to map specific locations that require mitigation. The table includes project data relevant to its identification/location, its prioritization, its cost, the timeframe estimated to complete, and the responsible agency. The timeframe includes the estimated completion period that starts when

### CUMBERLAND COUNTY HAZARD MITIGATION PLAN

funding is available and permitting has been obtained. Short term is 1 year, midterm is 2-3 years, and long term is 4-5 years before completion.

All municipalities understand that placing projects in the plan is no guarantee of their eligibility for grants or of federal funding.

In addition to stating whether the project is new, completed, deleted, or revised, the status column also identifies when FEMA funds were used for the project.

It should be noted that many urgently needed projects are not included here as they are on State roads and the towns do not have authority to do needed upgrades. In some instances, lengthy permitting processes are holding up needed work.

It should also be noted that in many instances, capabilities could expand if additional funding were to become available.

In the following projects list, completed projects move to the bottom of the list and newer projects are reprioritized.

Municipality	Project	Est. Cost	Timeframe	Responsible Official	Status
	1) Wentworth Rd: paving, culverts, ditching, shoulder work, reclaim, rip-rap, cut trees	\$175,000	Long Term	Road Commissioner	New Project
	2) Senator Black Rd: culverts, ditching, shoulder work, reclaim, rip-rap, cut trees	\$600,000	Long term	Road Commissioner	New Project
	3) Saddleback West Rd.; Remove trees from ditch line 3,500' add ditch 650' add 24" x 40' N-12 cross culvert.	\$9,000	Long term	Road Commissioner	Deferred – Lack of Funding
Baldwin	4) Anderson Rd; Add (2) 18" x 40' N-12 culverts and riprap inlet and outlet.	\$6,000	Mid tern	Road Commissioner	Completed 2014 with Town funds
	5) Brown Rd; Elevate road 925' x 21' x 3' add 24" x 40' N-12 culvert and stabilize shoulders. H&H study, engineering design, upgrade to 24" HDPE culvert, upgrade two 24" culverts to 57"x38" squash pipe	\$56,000 \$96,348.94	6 months	Road Commissioner &engineering firm	HMGP project Completed Oct 2012
	6) Senator Black Rd; Ditch 150' and upsize existing culverts.	n/a	2 weeks	Road Commissioner	Completed with Town funds per 2012 plan
Bridgton	1) Post Office Square (Main St-Depot St.); Upsize existing 48" x 50' culvert with 4' x 10' x 50' bottomless box culvert to match culvert under US 302. Revised: needs study and permitting from DEP, EPA, NFIP and USACE	TBD	Long term	Road Commissioner Engineering Firm	Revised from 2012 Plan
	2) Mountain Rd; Upsize existing triple culverts with 4' x 10' x 40' bottomless box culvert and riprap inlet and outlet. Replaced existing culverts	\$45,000	2 weeks	Road Commissioner	Completed with Town Funds

	1) Bull Rock Rd; Ditch and armor 400' add (2) 15" x 40' N-12 driveway culverts & an 18" x 40' N-12 cross culvert riprap inlet and outlet.	\$12,000	Long term	Director of Public Works	Deferred – Lack of Funding
Brunswick	2) Pleasant Hill Rd; Upsize twin 5' x 66' culverts w/ 12' x 6' x 70' bottomless box culvert w/ integrated headwalls.	\$175,000- \$200,000	Long term	Director of Public Works	Deferred – Lack of Funding
Dittilswick	3) Highland Rd. Upsize existing 24" x 40' culvert with 36" x40' N-12 culvert and riprap inlet and outlet.	\$25,000	Long term	Director of Public Works	Deferred – Lack of Funding
	4) Collins Brook Rd; Upsize existing 6' x 40' culvert with 8' x 5' x40' bottomless box culvert and riprap inlet and outlet.	\$33,868.80	3 weeks	Director of Public Works	Completed August 2014 town funds
	1) Kettle Cove Rd. @ Crescent Beach; Rebuild road substructure/retaining wall that abuts Crescent Beach	\$500,000	Long term	Director of Public Works	Revised from 2012 Plan and still deferred: lack of municipal funds
	2) Garden Circle. Improve gravity storm drain outfall and/or install stormwater pump station	\$125,000- \$1,100,000	Mid term	Director of Public Works	New Project
Cape Elizabeth	3) Oakhurst Rd & Hemlock Hill Rd.; Upsize 200' underground drainage. Add downstream stormwater catch basins on adjacent public way (Hemlock Hill Rd.) and replace current outfall	\$125,000	Long term	Director of Public Works	Revised from 2012 plan
	4) Sawyer St; Elevate 600' x 22' x 18" add (3) 18" x 40' N-12 cross culverts, stabilize shoulders and repave.	\$200,000	4 weeks Long term	Director of PW; Joint Project Scarborough	Deferred – Lack of Funding

	5) Garden Circle; Install pump system with vault and backup generator to remove ponding. Portland Water District installed grinder sanitary pump station, replaced existing catch basin with 4' diameter pipe. Outflow pipe being replaced with project #2	\$250,000	3 weeks	Director of Public Works	completed 2014 with PWD funds
	6) Spurwink Ave @ Spurwink River; Extend arch culvert.	unknown	unknown	Director of Public Works	Completed with Town funds per 2012 Plan
	7) Sawyer St. @ Trout Brook; upsize existing culvert with metal arch.	\$175,000	3 weeks	Director of Public Works	Completed with Town funds per 2012 Plan
	8) Scott Dyer Rd./ Elizabeth Park: Enlarge stormwater discharge outfall pipe.	unknown	unknown	Director of Public Works	Completed with Town funds per 2012 Plan
	9) Running Tide Rd; Sewer Rehabilitation project.	unknown	unknown	Director of Public Works	Completed with Town funds per 2012 Plan
	10) Old Ocean House Rd. @ Alewife Brook: Culvert Upgrade.	unknown	unknown	Director of Public Works	Completed with Town funds per 2012 Plan
	11) Spurwink Ave @ Trout Brook; Upsize existing culvert with metal arch culvert.	\$85,000	3 weeks	Director of Public Works	Completed with Town funds per 2012 Plan
Casco	1) Point Sebago Rd. Site #1; Add 24" x 40' N-12 cross culvert, ditch and line 200' and repave	\$4,000	Mid term	Road Commissioner	Deferred – Lack of Funding

	2) Johnson Hill Rd; Ditch and line 2,000', install check dams and upsize (4) 15" x 24' culverts w/ (4) 18" x 32' N-12 culverts. Road reconstruction scheduled	\$23,000	Short term	Road Commissioner	Deferred – Lack of Funding
	3) Leach Rd; Upsize existing cross culvert with 6'x 4' x 40' box culvert.	\$35,000	Long term	Road Commissioner	Deferred – Lack of Funding
	4) Edwards Rd Site #1; Elevate Road 300' x 2' x 21' upsize 36" x 40' corrugated metal pipe with 4' x 10' x 40' bottomless box culvert, repave and stabilize shoulders.	\$165,000	3 weeks	Road Commissioner	Completed 2013 with Town funds
	5) Edwards Rd Site #2; Upsize existing 24" x 40' corrugated metal pipe with 36" x 40' N-12 culvert riprap outlet.	\$5,000	2 weeks	Road Commissioner	Completed 2012 with Town Funds
	6) Edwards Rd Site #3; Riprap existing culvert.	\$1,000	1 day	Road Commissioner	Completed 2012 with Town Funds
	7) Point Sebago Rd. Site #2; Riprap inlet and outlet of existing culvert.	\$1,000	1 day	Road Commissioner	Completed 2014 with Town Funds
	8) Libby Rd; Elevate 200' x 21' x 2' stabilize shoulder and repave. Road reconstructed	\$18,000	3 weeks	Road Commissioner	Completed 2015 with Town funds
	9) Crooked River Corridor; Acquire and/or elevate 12 houses.	\$1,200,000- 3,500,000	6 months	Town Manager	Deferred - owners unwilling to sell at this time
Chebeague Island	1) Stone Wharf. Replace or relocate Chebeague island Ferry landing. Vulnerability Study complete; Engineering Study ongoing	\$300,000- \$1,000,000	Unknown Long term	Town Manager Road Commissioner	New Project

	2) Bennett Cove. Engineering Study for improvements to stone block commercial boat ramp	unknown	Long term	Town Manager Road Commissioner	New Project
	3) Indian Point Rd; Install sheet pile 500' x 10'.	\$14,000	Mid term	Road Commissioner	Deferred – Lack of Funding
	4) Ongoing public education of homeowners about protection from wildfires.	\$500	2016-2021	Fire Department & Island Institute Fellow.	Completed as planned; continuing
	1 ) Tuttle Rd Site 2; Elevate 200' x 21' x 3' stabilize shoulders and repave. Engineering Study completed	\$18,000	Long term	Director of Public Works	Deferred – Lack of Funding
	2) Middle Rd @ Hazeltines; Upsize existing 36" x 50' lined culvert with 42" x 50' N-12 culvert and riprap inlet and outlet.	\$17,000	Long term	Director of Public Works	Deferred – Lack of Funding
Cumberland	3) Tuttle Rd Site 1; Upsize existing 36" x 40' culvert with 48" x 40' N-12 culvert and riprap inlet and outlet.	\$14,000	2 weeks	Director of Public Works	Completed with Town funds
	4) Harris Rd; Upsize existing culvert with box and elevate road.	\$294,216.94	unknown	Director of Public Works	Completed with FEMA PA/ Town funds per 2012 Plan
	5) Range Rd. (5) sites Upsize culverts and improve inlet and outlets.	\$50,000	1 year	Director of Public Works	Completed with Town funds per 2012 Plan

	1) Northbrook Drive; Upsize existing 48" culvert with 8' x 4' x 80' bottomless box culvert and riprap inlet and outlet.	\$200,000	Long term	Director of Public Works	Deferred – Lack of Funding
	2) Middle Rd. @ Scittery Gussett Brook; Upsize triple 15" culverts with bottomless box culvert or as required by H&H study and riprap inlet and outlet.	\$100,000	Long term	Director of Public Works	Revised from 2012 Plan - held up for Army Corp of Engineering permit
Falmouth	3) Shoreline Drive Coastal Erosion; Stabilize bank 100' x 50' x 3' with large fractured stone Engineering study complete	\$75,000	Long term	Director of Public Works	Study -Town funds Deferred – Lack of Funding
	4) Woodville Road Piscataqua River Crossing; upsize double culvert with bridge or box culvert	\$500,000	Unknown	Director of Public Works	Completed with Town funds per 2012 Plan
	5) Woodville Rd @ High School; upsize existing culverts	\$50,000	1 week	Director of Public Works	Completed with Town funds per 2012 Plan
	1) Hunter Road. Upsize existing culvert with 24" culvert	\$125,000	Mid term	Director of Public Works	New Project
	2) Percy Street. Upsize existing culvert with 24" culvert	Unknown	Mid term	Director of Public Works	New project
Freeport	3) Richards Lane; Elevate 150' x 1' x 22' stabilize shoulders upsize twin 15" x 40' culverts with 6' x 3' x 40' bottomless box and riprap inlet and outlet.	Unknown	Long term	Director of Public Works	Deferred – Lack of Funding
	4) Grant Rd; Upsize existing culvert with 24" x 40' N-12 culvert.	\$4,000	3 days	Director of Public Works	Completed with Town funds
	5) Webster/Old County Rd; Install 36" x 50' N-12 culvert and riprap inlet and outlet.	\$5,000	1 week	Director of Public Works	Completed with Town funds

	6) Flying Point Rd; Enlarge existing corrugated metal pipe. Add additional culvert and elevate road and repave.	\$200,000-500,000	1 week	Director of Public Works	Completed with Town funds per 2012 Plan
	7) Cheehawk Rd; Added additional 18" x 40' N-12 culvert.	\$2,500	3 days	Director of Public Works	Completed with Town funds per 2012 Plan
Freeport Sewer District	1) move dry pit pump above ground and raise structure at least three feet.	\$300,000	Long Term	Board of Directors	New Project
Frye Island	1) Monitor/mitigate hillside erosion in Recreation Area trail between Beach 10 and Long Beach. Site monitoring will continue in order to collect more information and determine the best approach to mitigating the hazard.	Unknown	Long term	Director of Public Works	New Project
	2) Erosion at beach #6; Installed retention pond and added (2) culverts to divert flow from beach.	\$10,000	2 weeks	Town Manager	Completed with Town funds per 2012 Plan
	1) Mitchell Hill Rd; Elevate road 300' x 3' x 22' stabilize shoulders and upsize existing culvert with bridge approx. 100' x 22' with wing walls.	\$600,000	Long Term	Director of Public Works; Joint project with Scarborough	Deferred – Lack of municipal funds
Gorham	2) Dingley Springs Rd.; Upsize existing multiple culverts with 12' x 6 x 40' bottomless box culvert and riprap inlet and outlets.	\$80,000	Long Term	Director of Public Works	Deferred – Lack of Funding
	3) Wood Rd; Upsize existing multiple culverts with 12' x 6 x 40' bottomless box culvert and riprap inlet and outlets.	\$80,000	Long Term	Director of Public Works	Deferred – Lack of Funding
	4) Wilson Rd: Upsize existing culvert with 10' x 5 x 40' bottomless box culvert and riprap inlet and outlets.	\$60,000	Long term	Director of Public Works	Deferred – Lack of Funding

5) Buck St; Upsize existing multiple culverts with 20'x 8' x 40' bottomless box culvert and riprap inlet and outlets. Elevate road 200' x 21' x 3' and repave.	\$130,000	Long Term	Director of Public Works	Deferred – Lack of Funding
6) New Portland Rd; Upsize existing multiple culverts with 10' x 5' x 40' bottomless box culvert and riprap inlet and outlets.	\$60,000	Long Term	Director of Public Works	Deferred – Lack of Funding
7) Spiller Rd; Upsize existing multiple culverts with 20'x 8' x 40' bottomless box culvert and riprap inlet and outlets. Elevate road 200' x 21' x 3' and repave. Twin plastic culvert installed by PW	\$30,000	3 weeks	Director of Public Works	Completed in 2014 with Town Funds
8) Huston Rd; Upsize existing multiple culverts with 20'x 8' x 40' bottomless box culvert and riprap inlet and outlets.	\$75,000	2 weeks	Director of Public Works	Completed with Town funds per 2012 Plan
9) Tow Path Rd; Slope protection, upsize culvert.	\$20,000	2 weeks	Director of Public Works	Completed with Town funds per 2012 Plan
10) North Gorham Rd; Slope protection, upsize culvert.	\$20,000	2 weeks	Director of Public Works	Completed with Town funds per 2012 Plan
11) Hodgdon Rd @ South Branch Brook; Install metal arch pipe.	\$200,000	1 month	Director of Public Works	Completed with FEMA funds per 2012 Plan
12) Washburn Rd; Slope protection, upsize culvert.	\$20,000	2 weeks	Director of Public Works	Completed with FEMA funds per 2012 Plan
13) Longfellow Rd @ Indian Camp Brook; Slope protection, upsize culvert.	\$20,000	2 weeks	Director of Public Works	Completed with Town funds per 2012 Plan

Gorham, cont.

14) Day Rd @ Indian Camp Brook; Slope protection, upsize culvert.	\$20,000	2 weeks	Director of Public Works	Completed with Town funds per 2012 Plan
15) Weeks Rd @ Gully Brook; Slope protection, upsize culvert.	\$20,000	2 weeks	Director of Public Works	Completed with Town funds per 2012 Plan
16) Plummer Rd @ Westcott Brook; Slope protection, upsize culvert.	\$20,000	2 weeks	Director of Public Works	Completed with Town funds per 2012 Plan
17) New Portland Rd. @ East Branch of Indian Brook; Slope protection, upsize culvert.	\$20,000	2 weeks	Director of Public Works	Completed with Town funds per 2012 Plan
18) Flaggy Meadow Rd. @ Little River; Slope protection, upsize culvert.	\$20,000	2 weeks	Director of Public Works	Completed with Town funds per 2012 Plan
19) Brackett Rd.; Slope protection, upsize culvert.	\$20,000	2 weeks	Director of Public Works	Completed with Town funds per 2012 Plan
20) Files Road @ Files Brook; Scour protection.	\$20,000	2 weeks	Director of Public Works	Completed with Town funds per 2012 Plan
21) Brackett Rd @ Indian Brook; Additional scour protection and redesign bridge.	\$200,000	unknown	Director of Public Works	Completed with Town funds per 2012 Plan
22) Fort Hill Rd@ Tannery Brook; Additional scour protection and redesign bridge.	\$200,000	unknown	Director of Public Works	Completed with Town funds per 2012 Plan

	23) Deering Rd @ Stroutwater River; Slope protection, upsize culvert.	\$20,000	2 weeks	Director of Public Works	Completed with Town funds per 2012 Plan
	24) Hurricane Rd; Slope protection and upsize culvert.	\$20,000	Unknown	Director of Public Works	Completed with FEMA funds per 2012 Plan
	1) Campbell Shores Rd Site #1; Upsize triple 24" x 40' culvert with 4' x 8' x 40' bottomless box culvert raise road 21' x 3' x 500' and repave	\$60,000	Long term	Director of public Works	Deferred – Lack of Funding
Gray	2) Campbell Shores Rd Site #2; ;Upsize triple 24" x 40' culvert with 4' x 8' x 40' bottomless box culvert raise road 21' x 3' x 500' and repave.	\$60,000	Long term	Director of Public Works	Deferred – Lack of Funding
	3) Long Hill Rd.; Upsize 60" x 40' culvert with 5' x 8' x 40' bottomless box culvert, raise road 21' x 6' x 500' stabilize shoulders and repave.	\$70,000	Long term	Director of Public Works	Deferred – Lack of Funding - Engineering study – Town funds Possible DEP grant
	4) Westwood Rd at Sucker Brook; H&H, engineering design Upsize existing 36" x 40' culvert with 6' x 8' x 40' bottomless box culvert with integrated wing walls.	\$110,165.64	4 weeks	Director of Public Works & engineering firm	HMPG project completed Oct 2012
	5) Lawrence Rd; Elevate road 22' x 700' x 4' on average, raise bridge deck, stabilize shoulders and repave.	\$202,122.00	2 months	Director of Public Works / Town Engineer	Completed with town Funds August 2015

	1) Long Point Rd. Shore up embankment; engineering study done 2013	\$75,000	Mid term	Road Commissioner	New project
Harpswell	2) Bethel Point Rd.; Replace existing 8' x 40' culvert with same sized culvert.	\$149,000	2 months	Director of Public Works	Completed with Town Funds
Harrison	1) Buck Rd; Remove ledge in ditch line 300', continue berm along road and upsize existing twin culverts with 36" x 40' N-12 culvert.	\$9,000	Mid term	Road Commissioner	Deferred – Lack of Funding
Harrison	2) Fog Rd.; Upsize existing twin 36" x 40' cross culvert with 8' x 4' x 40' box culvert riprap inlet and outlet	\$9,000	Long term	Road Commissioner	Deferred – Lack of Funding
Long Island	1) 765 Island Ave; Engineering Study and upgrade culvert and stabilize outlet with riprap.	\$100,000	Long term	Road Commissioner	Revised from 2012 Plan
	2) Island Ave. & Garfield St; Install catch basin, add 18" x 40' N-12 culvert and upsize 15" x 40' culvert with 18" x 40' N-12 culvert. Ditch and armor 700' and shim 800' of road. Rebuild drainage grate	\$12,000	Long term	Road Commissioner	Revised from 2012 plan
	3)Beach Ave. Remove ledge 50' x 6' x 2' Ditch and line 200' add 12" x 30'N-12 driveway culvert	\$8,000	2 weeks	Road Commissioner	Completed with Town Funds
	4) Harbor De Grace St; Upsize 12" x 80' culvert with 15" x 80' N-12 culvert, remove ledge 30' x 6' x 2' and ditch 50'.	\$8,500	3 weeks	Road Commissioner	Completed with Town Funds

	5) Island Ave; Stabilize bank with riprap and native plantings 400' x 60' x 2'.	10,000	3 weeks	Road Commissioner	Completed with Town Funds
	6) Levitt Street/ Public Works Yard; Excavate wet spot in road install 12' x 30' filter fabric and crushed stone pillow.	\$8,000	3 weeks	Road Commissioner	Completed with Town funds per 2012 Plan
	1)—7) Island Ave @ Stepping Stone Ln.; Install 12" x 40 N-12 culvert and re-establish ditch line.	\$9,000	2 weeks	Road Commissioner	Completed with Town funds per 2012 Plan
	8) Apple Tree Ln.; Upsize existing cross culvert add (2) driveway culverts and (1) catch basin clean ditches and add check dams.	\$5,000	3 weeks	Road Commissioner	Completed with Town and PA funds per 2012 Plan
	Lakehouse Road near Muddy River ditching	\$3,500	Mid term	Road Commissioner	New Project
	2) Lamb's Mill Road from Rt 302 to hilltop ditching	\$3,000	Mid term	Road Commissioner	New Project
	3) Edes Falls Road and River Road junction 30"culvert upgrade and ditching	\$6,500	Mid term	Road Commissioner	New Project
	4) Wiley Rd @ Sam's Bluff; Upsize existing 30" x 40' corrugated metal pipe with 36" x 40' N-12 culvert and riprap inlet and outlet.	\$8,000	Long term	Town Manager	Deferred - Lack of funding
Naples	6) Songo Rd; Ditch 2,500' and add 30" x 40' N-12 culvert.	\$11,000	2 weeks	Town Manager	Completed with Town Funds
	7) Lambs Mill Rd; Remove road bed 200' x 21' x 12" install french drain and geotextile fabric and repave.	\$10,000	1 week	Town Manager	Completed 2012 with Town funds
	8) Horace Files Rd. @ Pikes Hill; Ditch 200' and build detention pond 10'x 10' x 6'.	\$2,000	1 week	Town Manager	Completed 2012 with

					Town funds
	9) Sand Rd; Upsize existing culvert with 24" x 40' N-12 culvert, remove catch basin and replace with stone lined plunge pool. New catch basin installed	\$5,000	1 week	Town Manager	Completed 2012 with Town funds
	1) Ayers Rd; Upsize multiple culverts with (1) 3' x 8' x 40' bottomless box culvert and (1) 3' x 10' x 40' bottomless box culvert, elevate road 300' x 21' x 2' and stabilize shoulders riprap and repave	\$116,000	Long term	Director of Public Works	Deferred - Lack of funding
New Gloucester	2) Durham Rd; Upsize multiple culverts with 3' x 8' x 40' bottomless box culvert, elevate road 600' x 21' x 2' and stabilize shoulders riprap and repave	\$73,000	Long term	Director of Public Works	Deferred - Lack of funding
	3) Woodman Rd; Upsize multiple culverts with 3' x 8' x 40' bottomless box culvert, elevate road 600' x 21' x 2' and stabilize shoulders riprap and repave.	\$60,000	1 month	Director of Public Works	Completed with Town funds
North Yarmouth	1) West Pownal Rd; Continue to monitor erosion at site (elevation of road would cost \$2 million). Site monitoring will continue in order to collect more information and determine the best approach to mitigating the hazard.		Long Term	Road Commissioner	Revised from 2012 Plan
Portland	1) Johanson and Front St; Park Side Condos acquisition and demolition of six unit condo complex.	1,000,000- 2,000,000	Long term	City Council	Deferred - Lack of funding
	2) Washington Ave. @ Leister Dr; Upsize, realign and lower outlet 36" x 150' corrugated metal pipe with 48" x 150' N-12 culvert and install plunge pool.	\$50,000	Long term	Director of Public Works	Deferred - Lack of funding

_					
	3) Gertrude St. Install backflow prevention.	\$500,000	Long term	Director of Public Works	Deferred - Lack of funding
	4) Capisic St.; Install backflow prevention.	\$500,000	Long term	Director of Public Works	Deferred - Lack of funding
	6) Back Cove @ Tukeys Bridge; Stabilize bank along back cove 100' x 90' x 3' using one ton fractured stone and flat revetments in the water up to 5' above mean high tide.	\$180,000	2 months	Director of Public Works	Completed City funds
	7) Back Cove @ Dartmouth St; Stabilize bank erosion along walking trail 6'x 150' x 2' using 500 lb. fracture stone riprap.	\$14,256	1 week	Director of Public Works	Completed City funds
	8) West end Commercial St; Upgrade drainage.	\$500,000	Unknown	Director of Public Works	Completed with City funds per 2012 Plan
	9) Alden and Violette St; Upsize culverts, build detention pond upstream and install backflow valves.	\$1,000,000	Unknown	Director of Public Works	Completed with City funds per 2012 Plan
	10) Alden @ Violette Circle; Upsize Lucas St culvert, build detention ponds upstream and install backflow preventers.	\$1,000,000	Unknown	Director of Public Works	Completed with City funds per 2012 Plan
	11) Mona/Bernard/Washington/Maine Ave. @ Falls Brook; Easement acquisition, culvert upgrades and stream channel work.	\$8,000,000	Unknown	Director of Public Works	Completed with City funds per 2012 Plan
	12) West end of Commercial St; Upgrade storm water system.	\$1,000,000	Unknown	Director of Public Works	Completed with City funds per 2012 Plan

	13) 60 kW Generator for Munjoy Fire Station to power 100% of building Also protects sprinkler system for Portland observatory which is wired into Fire Station	\$93,655	24 weeks	City of Portland	HMPG Grant funding Completed 2015
	1) Chadsey Rd Site #1 Upstream; Upsize triple N-12 culverts with 12' x 4' x 40' bottomless box culvert and riprap inlet and outlets.	\$45,000	Long term	Road Commissioner	Deferred - Lack of funding
Pownal	2) Chadsey Rd Site #2; Upsize triple N-12 culverts with 12' x 4' x 40' bottomless box culvert and riprap inlet and outlets.	\$45,000	Long term	Road Commissioner	Deferred - Lack of funding
	3) Brown Rd; Upsize twin 48" x 40' culverts with 12' x 4' x 40' bottomless box culvert, riprap inlet and outlets and repave.	\$48,000	Long term	Road Commissioner	Deferred - Lack of funding
Raymond	1) Monitor/mitigate as needed ditch erosion at Raymond Hill Rd and Webbs Mill Rd Site monitoring will continue in order to collect more information and determine the best approach to mitigating the hazard.	Unknown	Long term	Road Commissioner	New Project
	2) Plains Road at Route 85 & Crescent Beach; Install closed drain and catch basin	\$50,000 - \$200,000	3 weeks	Director of Public Works	Completed with Town Funds
	3) Mountain Rd from Spiller Hill to McDermott Drive; Upsize culvert and armor ditch.	\$20,000 - \$50,000	2 Weeks	Director of Public Works	Completed with Town funds per 2012 Plan
	4) Elizabeth Ave. from Route 302 to Pine Road	Unknown	Unknown	MDOT	Completed with State funds per 2012 Plan

## Scarborough

1) Gorham Rd at Nonesuch River. Engineering study and replacement of existing 5' culvert	\$200,000 - \$300,000	Long term	Director of Public Works	New Project
2) Payne Road at Cabela's Boulevard. Engineering study and upsizing of drainage culverts	\$75,000 - \$175,000	Long term	Director of Public Works	New Project
3) Pleasant Hill Upgrade storm drain system.	\$600,000	Long term	Director of Public Works	Revised from 2012 Plan
4) Broadturn Rd & Martin Ave; Upsize existing twin 36" x 40' corrugated metal pipes with 10' x 4' x 40' bottomless box culvert and add 36" x 40' N-12 culvert on Martin Ave.	\$65,000	Long term	Director of Public Works	Deferred - Lack of funding
5) Mitchell Hill Rd; Elevate road 300' x 3' x 22' stabilize shoulders and upsize existing culvert with bridge approx 100' x 22' with wing walls.	\$600,000	Long term	Director of Public Works; Joint project with Gorham	Deferred - Lack of funding
6) Sawyer St.; Elevate 600' x 22' x 18" add (3) 18" x 40' N-12 cross culverts, stabilize shoulders and repave.	\$95,000	Long term	Director of Public Works; Joint project with Cape Elizabeth	Deferred - Lack of funding
7) Higgins Beach along Bay View Dr; shoreline erosion. Install plantings/storm breaks.	\$75,000	3 weeks	Director of Public Works	Completed with FEMA/ Town funds. Still Issues. per 2012 Plan
8) Higgins beach between Cliff and Shell St; Upgrade storm drain system.	\$100,000	Unknown	Director of Public Works	Completed with Town funds per 2012 Plan
9) Clay Pitts Rd; Armor river banks with riprap	\$7,500	3 weeks	Director of Public Works	Completed with FEMA/ Town funds per 2012 Plan

1 Shore Road: 600' surface improvements, add gravel cross culverts	\$100,000	Short Term	Road Commissioner	New Project
2. Anderson Road: ditch, cross culverts and repave	\$90,000	Long Term	Road Commissioner	New Project
3. Robinson Hill Rd.: rebuild cross culverts under drains (spring), ditch both sides of road, repave	\$225,000	Short Term	Road Commissioner	New Project Completed with Town Funds
4 Swamp Road: ditch both sides of road, cross culverts and repave	\$165,000	Short Term	Road Commissioner	New Project completed with Town Funds
5) Peabody Pond Rd. Ditch and line 1,800' add (2) driveway culverts 15" X 30' and (42) cross culvert 15" x 40' remove ledge from ditch line. Second cross culvert 4' x 45"	\$75,000	2 weeks	Road Commissioner	Revised from 2102 Plan In progress
6) River Rd; Elevate and reconstruct road replace 18" x 40' culverts with 24" x 40' N-12 culverts.	\$120,000	3 weeks	Road Commissioner	Completed with Town Funds
7) Hancock Pond Rd; Upsize culvert and elevate road and add ditches. Ditched on both sides and repaved 3.6 miles	140,000	3 weeks	Road Commissioner	Completed with Town Funds
8) Winn Mountain Rd; Ditch 500'. Ledge blasting to improve drainage	\$5,000	1 week	Road Commissioner	Completed with Town Funds
9) Dyke Mountain Rd; Ditch and pave road.	\$67,000	1 week	Road Commissioner	Completed with Town funds per 2012 Plan
10) Orchard Rd; Ditching and install 140' of culverts.	\$8,000	1 week	Road Commissioner	Completed with Town funds per 2012 Plan

South Portland	1) Fessenden St @ Trout Brook; Upsize existing twin 36" x 50' culvert with 3' x 8' x 50' bottomless box culvert and riprap inlet and outlet.	\$65,000	Long term	Director of Public Works	Deferred - Lack of funding
South Portland Cont.	2) Alfred St; Upsize existing twin 24" x 40' culvert with 3' x 6' x 50' bottomless box culvert and riprap inlet and outlet.	\$55,000	Long term	Director of Public Works	Deferred - Lack of funding
	3) Boothby St @ Trout Brook; Upsize existing culvert with 3' x 6' x 50' bottomless box culvert and riprap inlet and outlet.	\$55,000	Long term	Director of Public Works	Deferred - Lack of funding
	4) Running Hill Rd; Install catch basin.	\$25,000	Mid term	Director of Public Works	Deferred - Lack of funding
	5) Broadway @ Daytona; Relocate Basin	\$50,000	unknown	Director of Public Works	Completed with City funds per 2012 Plan
	6) Highland Av @ High school; Upgrade storm drain system.	\$130,000	unknown	Director of Public Works	Completed with City funds per 2012 Plan
	7) Main St @ Massachusetts and Main @ Wallace Ave.; Road rehabilitation	Unknown	unknown	Director of Public Works	Completed with City funds per 2012 Plan
	8) Preble @ Alder and Day St; Add curb inlet.	\$10,000	unknown	Director of Public Works	Completed with City funds per 2012 Plan
	9) Broadway @ Boys Club; New sidewalks and upgrade systems.	\$50,000	unknown	Director of Public Works	Completed with City funds per 2012 Plan

10) Highland Ave @ Whispering Pines; Upgrade storm drain system.	\$100,000	unknown	Director of Public Works	Completed with City funds per 2012 Plan
11) Broadway @ underpass; Upgrade Storm drain system.	\$100,000	unknown	Director of Public Works	Completed with City funds per 2012 Plan
12) Dike Farm Rd @ Meadow Way; Upgrade storm drain system.	\$50,000	unknown	Director of Public Works	Completed with City funds per 2012 Plan
13) Nutter Rd; Upsize existing culvert.	\$10,000	unknown	Director of Public Works	Completed with City funds per 2012 Plan
14) Highland Ave @ Gamblers Brook; Upsize existing culvert.	\$10,000	unknown	Director of Public Works	Completed with City funds per 2012 Plan
15) Angell Ave. @ Preble St; Install curb inlets.	\$50,000	unknown	Director of Public Works	Completed with City funds per 2012 Plan
16) Cummings Rd @ Westbrook Line; Upgrade culverts.	N/A	unknown	Director of Public Works	Completed with City funds per 2012 Plan
17) Broadway @ Scarborough Line; Upgrade Ditches.	N/A	unknown	Director of Public Works	Completed with City funds per 2012 Plan
18) Willow St @ Sand pebbles condo's; Tidal effect	N/A	unknown	Director of Public Works	Completed with City funds per 2012 Plan

Standish	1) Blake Rd; Upsize existing twin culverts 36" x 40' culverts with 8' x 4' x 40' bottomless box and riprap inlet and outlet	\$70,000	Long term	Director of Public Works	Deferred - Lack of funding
Standish cont.	2) Middle Jam Rd; Install precast head wall with wing walls on inlet and outlet of 40" culvert.	\$15,000	Mid term	Director of Public Works	Deferred - Lack of funding
	3) Northeast Rd @ Rt. 35; Ditch and armor 300' add 30" x 30' N-12 driveway culvert.	\$7,000	Mid term	Director of Public Works	Deferred - Lack of funding
	4) Route 35A – Cape Road; upsize culvert, create spillway, armor downstream side of road bed.			Director of Public Works	Deferred - Lack of funding
	5) Cape Rd; Upsize existing 30" x 40' corrugated metal pipe with 36" x 40' N-12 culvert and riprap inlet and outlet.	\$5,000	2 week	Director of Public Works	Completed with town funds
	6) White Bridge Rd; Upsize existing culvert and create spillway and armor downstream side of road.	\$ 50,000-200,000	3 weeks	Director of Public Works	Completed with Town funds per 2012 Plan
Westbrook	Brook Street. Replace bridge over Minnow Brook with new culvert to meet crossing standards	Unknown	Long term	Director of Public Works	New Project
	2) Cottage Place. Culvert upgrade to meet crossing standards.	Unknown	Long term	Director of Public Works	New Project

	3) Purchase and demolish building at 40 Lincoln St.	\$250,000	Long term	Director of Public Works	New Project
	4) Cumberland St; Upsize existing twin culverts.	Unknown	Unknown	Director of Public Works	Completed with City funds per 2012 Plan
	5) River Walk @ Ash St; Stabilize bank with 12" riprap.	\$5,000	3 Days	Director of Public Works	Completed with City funds per 2012 Plan
Windham	1) Highland Cliff Rd @ Annie Leighton Brook. Add second culvert	\$45,000	Long term	Director of Public Works	Revised from 2012 Plan
	2) Nash Rd; Elevate road 1,200' x 21' x 2' stabilize shoulders add 24" x 40' N-12 cross culvert and repave.	\$74,000	Mid term	Director of Public Works	Deferred - Lack of funding – now in capital budget
Yarmouth	1) Ledge Rd; Install headwall and wing walls on inlet side of Pratt's Brook.	\$10,000	Mid term	Director of Public Works	Deferred - Lack of funding
	2) North Rd; Add 42" x 80' N-12 overflow culvert at Pratt's Brook.	\$15,000	2 weeks	Director of Public Works	Completed with Town Funds

# CUMBERLAND COUNTY HAZARD MITIGATION PLAN

3) Pratt's Brook @ Northwood Rd; Problem should be solved by adding overflow culvert @ North Rd.	N/A	N/A	Director of Public Works	Resolved by North Rd culvert
4) Pratt's Brook @ East Elm St; Problem should be solved by adding overflow culvert @ North Rd.	N/A	N/A	Director of Public Works	Resolved by North Rd culvert